



TexasSaratoga + | TXSG+

PROPERTY	UNITS	DESCRIPTION
COLOR		Field Green + Olive Green & Field Green + Jute
ROLL SIZE	13 FT x 100 FT	
PERMEABILITY TYPE		Approx. 30 in. per hour
PILE HEIGHT	1 3/4 in	
GAUGE	3/8 in	
STITCHES/SQ METER	24.150	
FIBER WEIGHT	60 oz/yd ²	
TOTAL WEIGHT	79.5 oz/yd ²	
PRIMARY BACKING		100% PP, UV stabilized, approx 160 gr +/- 10%
COATING		SBR latex, approx 685 gr. / m ² +/- 10%

COLOR

BLUESCALE 1-8 > 7 (DIN 54004)

GREYSSCALE 1-5 > 4 (DIN Standard)

FG + OG and FG + Jute

MATERIAL

100% PE monofilament, microcurled

7.250 Dtex / 14 ply

100% European product, free of heavy metals and toxins

